


A Landscape Transformed: Lock 4 Canal Park

**The Construction of Champlain Barge Canal
Lock 4, and the Alteration of the Junction of
the Hoosic and Hudson Rivers**

Rensselaer-Taconic Land Conservancy
2000



Lock 4 Canal Park, owned by the New York State Canal Corporation, is located in the Town of Schaghticoke, Rensselaer County, at Lock 4 of the Champlain division, where the Hoosic River enters the Hudson opposite Stillwater. Before the construction of the Lock in 1908-1912, three shale bluff islands existed at this confluence. The canal construction significantly altered the landscape, transforming two of these islands into part of the mainland. While the area is still highly scenic, the configuration and use of the land has changed markedly. Barge Canal records held by the New York State Archives are used to document these land changes and the canal construction process.

The New York State Canal System we know today had its roots in the Western and Northern Inland Lock Navigation companies, which established a crude transportation system in the late Eighteenth and early Nineteenth centuries. This route followed navigable rivers and streams, connected in places by rather short artificial canal passages. Interest in developing a statewide canal system developed about the time of the War of 1812, and work began on the first Erie and Champlain Canals in 1817. The Erie Canal was finally completed between Albany and Buffalo in 1825 and the Champlain Canal was completed between Cohoes and Whitehall in 1823. The Erie Canal was used so heavily in its early years that it was enlarged, and in some places relocated, between 1835 and 1862. A number of lateral canals were constructed in the Nineteenth Century as well, mostly connecting to the Erie Canal.

By the 1890s the canal system had become outdated and another major enlargement project was begun in 1895. This project was halted three years later, and then Governor Theodore Roosevelt authorized a study, issued in 1900, which recommenced the construction of an entirely new modern canal system. This culminated in the construction and operation of the New York State Barge Canal System, which was completed in 1918. The construction of the Barge Canal came under the jurisdiction of the State Engineer and Surveyor, State Superintendent of Public Works, and State Canal Board. In 1992 jurisdiction over the Barge Canal system was transferred from the State Department of Transportation to the New York State Thruway Authority, which operates the present-day canals through a subsidiary, the New York State Canal Corporation. The name "Barge Canal" was dropped and the entire network is now known as the New York State Canal System.

The Erie Canal of the Nineteenth Century has become famous for the remarkable role it played in expanding commerce and developing communities in central and western New York, and has been memorialized in literature, lore and song. Its sister canal, the Champlain Canal of the same era, is far less known and renowned. The Barge Canal system is also far less famous, possibly because of its creation in a more modern, technological era lacking the drama and romance associated with the old Erie Canal. Only two major published works have been devoted to the Barge Canal System: Noble Whitford's *History of the Barge Canal System of New York State*, a state document issued in 1922, and Michele McFee's recent illustrated history, *A Long Haul, the Story of the New York State Barge Canal*, published in 1998.

In one way, the Twentieth Century Barge Canal more closely resembled the early inland water navigation system than the old Erie and Champlain canals. While the Nineteenth Century canals were largely self-contained, the Barge Canal system followed rivers and other navigable waterways wherever possible. In many places, rivers such as the Hudson and Mohawk required damming and dredging to provide a dependable channel deep enough for vessels. The Champlain division of the Barge Canal followed the Hudson River from Lansingburgh/Waterford as far north as Fort Miller and Fort Edward, where it followed an artificial channel to its terminus at Whitehall. A series of seven dams and associated locks were constructed in the section, and for the most part the course of the Hudson River was not greatly altered. These dams were largely located at the site of older dams in the Hudson, where low rapids were present in the river.

This was the case at Champlain Locks 1, 2, and 3 located between Rensselaer and

Saratoga counties. At Locks 1 and 2, small islands were incorporated into the lock infrastructure, but the general course of the river remained unchanged. The highly scenic islands in the "horseshoe bend" in the Hudson immediately below Lock 1 appear today as they have from the times they were used first by Native American and later by local Nineteenth Century farmers. This was not the case, however, at Champlain Lock 4 opposite Stillwater, where the construction of the Barge Canal lock led to a significant alteration of the landscape.

The subject of our study is Lock 4 Canal Park, the largest park operated by the Canal Corporation, comprising about 91 acres of land located at the junction of the Hoosic and Hudson Rivers. The park includes a picnic area, observation platform at the lock, a canoe launch, and short nature trails. The area is highly scenic, where shale bluffs overlook the Hoosic River raging over a series of rapids immediately before entering the Hudson. The park has been identified by the New York State Natural Heritage Program and the Rensselaer-Taconic Land Conservancy as a significant plant habitat, containing a wide diversity of species, including some state-listed rare plants. The park is located entirely within the Town of Schaghticoke, Rensselaer County, while the adjacent privately-owned Green Island is located in the Town of Stillwater.

Green Island is the only remaining island not substantially altered by the lock construction. The other two original islands, sometimes known as Parry's Island and Vandenberg's (or Bulson's) Island, have become peninsulas attached to the mainland. These islands first appear on "A Map of the Corporation Lands at Schatikooke," copied for Harmen Gansevoort in the 1790s by Simeon De Witt, one of the Survey Maps of Lands in New York State. This map seems to depict four islands, where in reality only three appear to have ever existed. Of particular interest is a former channel between the mainland and Vandenberg's Island known as the "Dwaas Kill," a name of Dutch origin meaning a stream that flows at a transverse angle to another watercourse. Local legend recalls that water in the Dwaas Kill flowed either from the Hoosic to the Hudson, or in the other direction, depending on water flow in both rivers, creating a series of dangerous rapids. Even with the construction of a low dam at Stillwater, this landscape remained unchanged until the Barge Canal construction took place.

While these islands do not appear on most 19th century maps, the area is shown in great detail on five of the so-called "Egg-shell Maps" (Erie and Champlain canals topographic survey maps), which date from shortly after 1900, and are held by the State Archives. These maps also show the proposed route of the Barge Canal cut, which bisected Vandenberg's Island. As the computer-generated maps indicate, the passage between Parry's and Vandenberg's islands was blocked, and the low area is today a wetland. The Dwaas Kill was also blocked off and was nearly obliterated. A new bridge was constructed at Stillwater and an access road to the lock was opened. The Kipp house, located close to the canal cut at its north end, was demolished.

The Barge Canal work was accomplished primarily through contract #68, issued to the firm of Shanley-Morrissey, Inc. of New York City in 1908 for \$947,813. Dredging of the Hudson from Lock 2 north to Lock 4 was begun in 1909 under contract #72 for \$618,900 by the same firm, but they were not able to complete this job. As a result, contracts 72A (for \$1,515,095) and 72B (for \$92,517) were awarded to another New York City firm, James Stewart & Co., in 1913 and 1916 respectively. This work also included widening the prism at the mouth of the Hoosic River.

The New York State Archives holds a number of series of records relating to the design and construction of the Barge Canal system. Sample records from the following eight series are reproduced here:

- 14068. Erie and Champlain canals topographic survey maps ("egg shell maps"), ca. 1904-1915.
- B0391. Barge Canal contract location maps, ca. 1904-1905.
- 10448. Maps, drawings and blueprints related to State waterways and canals, ca. 1851-1941.
- B0214 Barge Canal Land Appropriation Maps, 1910-25 (recent accretion)
- B0392. Charts and maps of the State canal system, ca. 1923.
- B0213. Barge Canal contract files, 1907-1944.
- B1009. New York State Barge Canal plans, 1920.
- 11833. Barge Canal construction photographs, 1905-1921.

Descriptions of these records are taken from the New York State Archives publication *The Mighty Chain* (1992).

coffer dam: an artificial structure used to keep water away from an enclosed area when underwater construction is taking place.


prism: as used in this context, an artificial cut or bore through earth and rock which becomes part of a canal when completed.

At the conclusion of this publication are listed other selected series of records relating to the Barge Canal system. While these series do not contain significant information on the construction of Champlain Lock 4, they are very useful in documenting the planning and construction of other parts of the Barge Canal system. Most all canal records held by the New York State Archives are described in the New York State Archives publication *The Mighty Chain: A Guide to Canal Records in the New York State Archives* (1992). Only a few examples from the ca. 700-800 cubic feet of records held by the New York State Archives relating to the Barge Canal are shown here. Using this study as an example, I recommend that New York State residents use these series of the New York State Archives records and other original documentary source materials to unlock the fascinating history of the development, construction and use of the Barge Canal system across the state.

compiled by Warren F. Broderick
March, 2000

A portion of "A Map of the Corporation Lands at Schaghticoke, copied by Simeon De Witt, Esquire by Harmen Gansevoort," (ca. 1790-1800), shows the islands at the confluence of the Hoosic and Hudson Rivers. Note the "saw mill" located near the Dwaas Kill. The Wynant Vandenbergh house shown nearby, constructed in 1732, stands today on River Road (County Route 120) just north of Stillwater Bridge Road (County Route 125). Office of State Engineer and Surveyor, Survey Maps of Lands in New York State ("Surveyor General Maps"), New York State Archives, Series # A0293, map # 97.





Lock 4 Canal Park

view before construction of Barge Canal

Computer-generated maps, created in the R-TLC's geographic information system (G.I.S.), show the area before and after the construction of the Barge Canal between 1908 and 1918. While the landscape was significantly altered by this project, the wild, scenic character of the junction of the rivers and portions of the three islands remain.


Series # 14068. Erie and Champlain canals topographic survey maps ("egg shell maps"), ca. 1904-1915. 40 cu. ft. Arrangement: By canal, then numerical by assigned number.

Commonly referred to as "egg shell maps" because of the paper on which they were executed, these maps depict in minute detail lands adjacent to the Erie and Champlain canals during the time of their enlargement and improvement as the Barge Canal. The maps apparently date from the time of the initial Barge Canal Law of 1903 (Chapter 147). They show the routes of the proposed new canals, and often the existing canals as well.


The purpose of these maps appears to have been to provide an accurate depiction of the land taken up by and surrounding the canal in order to determine both private and State ownership of land, and to provide the most accurate survey measurements possible for the canal enlargement and improvement. The maps show blue lines representing State-owned land; red lines representing the inner line of the towpath; green lines representing a new channel line (when dotted) or a potential flood line (when solid); contour lines, land elevations, and depths of bodies of water; and lines showing boundaries of specific work contracts.

Some maps occasionally depict property lines, parcel numbers, and names of property owners; outlines of buildings, sometimes with names; location of existing canal structures and railroad and telegraph lines; and swamps, fens, and other natural phenomena. One hundred two maps depict the Erie Canal from Waterford to Morris Island (just west of Pattersonville). Fifty-four maps depict the Champlain Canal from Northumberland to 101st Street in Lansingburgh. Most maps appear to have a scale of 1 inch = 100 feet, although some have a scale of 1 inch = 50 feet.

The following map is a montage of five maps from this series, depicting the area which would become Lock 4 of the Champlain Division. Both rivers, three islands and the passages between them are clearly visible. This map was used to create the computer-generated map showing the area before Barge Canal construction. The location of the path of the proposed canal is drawn on these maps, including the portion where the prism needed to be blasted through the shale rock.



Map # 28 of the "Eggshell Maps" shows the junction of the Hoosic and Hudson Rivers, at the former Vandenberg's (Bulson's) and Parry's islands. The bluff on the southern end of Vandenberg's Island (currently a peninsula) now features a nature trail where one may view the rapids in the adjacent Hoosic River.



POOL EL. 675
GRADE EL. 535

ISAAC KNAPP ESTATE

Samuel Perry
28.4 Acres Parcel No 2026

C.E. SULSON

C.E. SULSON

C.E. SULSON

Series # B0391. Barge Canal contract location maps, ca. 1904-1905. 2 cu. ft. (18 volumes consisting of one colored map in numerous sections on 18 sheets)

The series consists of cut up sections of a printed U.S. Geological Survey topographic map of New York State that has been annotated to locate the areas covered by Barge Canal contracts. The map sections are undated but the series apparently complies with specific requirements of section four of the Barge Canal Law (Laws of 1903, Chapter 147). This law directed that all authorized canal work be done by contract, and that before any contract could be made the State Engineer must divide the whole work into sections suitable for contracting, and make maps, plans, and specifications for the work to be done.

Each of the three canal divisions and the separate canals on each division were divided into residencies, with work in each residency done under the direction of a resident engineer or an assistant engineer in charge. In 1904 the canal line was divided into 15 sections or residencies for conducting work in the field; the presence of residency numbers dates the series from approximately that time.

Annotations are by hand and in color, and were apparently made on a single topographic map of the entire State that was subsequently cut up. Contract numbers and the area covered by each contract are marked in red, with the names of respective contractors marked below them in black. Maps also provide residency numbers and these areas are marked by bars of color that remain constant throughout all map sections.

This map shows the entire route of the proposed Barge Canal between its beginning in the Hudson River opposite Lansingburgh, northward to the county line. The location of the site of the remarkable "Waterford Flight" of locks on the Erie Division is also visible. Note the remains of an old dam, since washed out, on the Hoosic River near the Dwaas Kill entrance. This dam may have been used to divert water to the early saw mill shown on the Gansevoort/De Witt map shown on page 5.


Series # 10448. Maps, drawings and blueprints related to State waterways and canals, ca. 1851-1941. 24.8 cu. ft. Arrangement: None. Finding aids: Item list.

This series is an assortment of maps, profiles, tracings, sketches, plans, drawings, blueprints, and a small quantity of related charts and correspondence relating to the State's canals, feeders, and/or various waterways. Proximity to canals and/or placement of the lands, structures, and watercourses adjacent to them is the only common element apparent in these varied representations.

The series includes profiles of canals and rivers; cross sections of actual and proposed canal and railroad lines; canal section maps showing centerline and survey offset lines and measurements; maps showing city, county, and town railroads and street railways in relation to canals, including one distinctive group that highlights several railroads along the Erie Canal and also shows adjacent land for a considerable distance; construction and improvement plans for a myriad of projects such as dredging water bottoms, altering or extending railway or canal lines or routes, deepening or changing canal channels, or building related structures; operating diagrams and blueprints for proposed and existing reservoirs, dams, locks, spillways, piers, lighthouses, docks, pipelines, roads, etc.; general location maps of aqueducts, bridges, buoys, etc.; sketches of harbors, slips, basins, and terminals; maps or tracings of reservoirs, rivers, and other bodies of water; drawings of bridges crossing canals; detailed sketches of the location of canals, drainage patterns, and areas of cultivated land, sometimes showing names of property owners, specific crops, and/or condition of land; representations of characteristics (elevations, water levels, catchment areas) and related structures (bridges, dams) of various creeks, rivers, lakes, and watersheds.

This series of miscellaneous documents includes a "profile map," showing in this section the canal route in the Mechanicville-Stillwater area, showing water depths and pool levels between Locks 2 and 4. The contract areas are also shown, as well as the vertical lift necessary at each lock.

STILLWATER



LOCK No. 3.

LOCK No. 4
(STILLWATER)

(UPPER MECHANICVILLE)

CONTRACT No. 68

THURN LIMIT OF CONTRACT NO. 72
THURN LIMIT OF CONTRACT NO. 73

CONTRACT No. 68

Series # B0214. Barge Canal Land Appropriation Maps, 1910-25. 15 cu. ft. Arrangement: Numerical by contract number. Finding aids: Container list.

This series documents the responsibilities of the Superintendent of Public Works relating to the appropriation of land for canal use. The series consists of duplicates of the original appropriation maps filed in county clerks' offices; descriptions of lands to be appropriated; county clerks' certificates of filing; notices to be served on property owners (informing them that the State Engineer and Surveyor has filed the necessary appropriate documents with the Superintendent of Public Works); and affidavits of service.

The maps provide a detailed view of the property to be appropriated. Each map includes the names of property owners (or reputed owners) and often the names of adjoining property owners; a detailed narrative description of the lands to be appropriated, written directly onto each map; and a standard title that includes the town and county of the land to be appropriated. In addition, the maps sometimes include land acreage; statements relating parcels to numbered line stations; an indication of iron pipes (from which parcel measurements were taken); the monumented base line (a line parallel to the center of the improved Erie Canal); and lines designating proposed pipe lines, the old Erie Canal, the improved Erie Canal and other features such as railroad lines.


The recent accretion (transferred from the New York State Canal Corporation) consists of approximately 475 blueprint maps (ca. 8 1/2 x 11") mounted on linen backing. The maps are divided by the traditional canal divisions (Eastern, Middle and Western) and then organized into so-called "books" by the specific canal name. Each "book" includes a key map of the particular geographic area it covers. Individual maps show the right of way of the Barge Canal and the property acquired by the State for its construction including name of the property owner, claim number, and acreage of the parcel. Most of the maps are drawn to the scale of 1" = 500 ft.

This map (from the recent accretion) provides an excellent overview of the study area, while showing the lands appropriated for the Barge Canal construction. Only a portion of Parry's Island was appropriated; one part of the island remains in private hands, while the other became part of Lock 4 Canal Park.

Series # B0392. Charts and maps of the State canal system, ca. 1923. 1 cu. ft. (1 volume containing 64 colored maps and charts) Arrangement: Numerical by map number and roughly geographical from eastern to western New York.

This series consists of 64 charts and copies of maps of the Erie Canal from Waterford to Buffalo, and of the Champlain, Oswego, and Cayuga-Seneca canals. They were apparently prepared to aid ships or boats in navigating canal waterways. Original navigation charts are mixed with copies of survey maps that might have been intended to aid production of charts for additional uncharted canal areas. All of the navigation charts follow a similar format. Printed base maps prepared from surveys made by the State Engineer and Surveyor date from 1917 to 1925. The base maps show city, village, town, and county boundaries, bodies of water and islands, roads and bridges, railroads, and streets and buildings, and are hand annotated to show location and type of buoys and buoy numbers. In addition, there are unannotated blueprint copies of survey maps. These pick up where the charts leave off, at a geographical point near Palmyra where the Erie Canal leaves the Seneca River, the point where the artificial cut of the canal begins.

Map #53 shows the Champlain division of the Barge Canal between Lansingburgh/Waterford and Stillwater. The portion showing the Lock 4 area is reproduced here.



CHAMPLAIN CANAL SHEET 1

Series # B0213. Barge Canal contract files, 1907-1944.
85 cu. ft. Arrangement: By type of contract, then numerical by
contract number. Finding aids: Container list.

These files concern the review, implementation, administration, and supervision of contracts entered into by the State for construction of the Barge Canal and canal terminals. Types of records routinely found within the files include contracts; correspondence; memoranda; contract specifications and alterations; general contract descriptions; estimates (both preliminary and final); calculations; bid proposals; inspectors' reports; engineers' monthly reports; employee time rolls; results of chemical and physical tests on construction materials; photographs of construction in progress; copies of engineering journals; construction equipment catalogs; invoices; and surveys.

Selected documents from this very important series are reproduced here. The first, "Estimated Values of Appropriated Lands" for Contract # 68, describes the property condemned for the canal construction. On the Kipp property, only a small piece of land was not directly affected, rendering the house remaining there of little value. Therefore the house was purchased and razed by the State.

Contract No. 68 Location: Town Schaghticoke County Pennsylvania

(A) Farm including house and barns and all area is assessed at \$1000 - Say house and barns \$500 and land \$500
(B) Property including house and barn and all area of land is assessed at \$1000 - Say house and barn \$500 and land \$500
(C) Farm including house and barns and all area of land is assessed at \$1000 - Say house and barn \$500 and land \$500
(D) Farm including house and barns and all area of land is assessed at \$1000 - Say house and barn \$500 and land \$500
(E) Property including 145 acres of land assessed at \$1000.

Contract files typically contain preliminary estimates for materials used in the construction project, and sometimes an overall structure sketch. The Preliminary Estimate of Quantities and Cost gives an idea of the total of materials needed for the construction of Champlain Locks 3, 4 and 5. The summary of quantities provides a more detailed breakdown.

ITEMIZED PROPOSAL—CONTRACT No. 65—(Continued).

ITEM No.	QUANTITIES	ITEMS	PRICE		AMOUNT	
			Dolls.	Cts.	Dolls.	Cts.
27	1,150	Lin. Ft. Wooden Fence Per Lin. Ft.		20	230	00
28	1,300	Lin. Ft. Drilling Bolt Holes in Rock Per Lin. Ft.		60	780	00
29	For Raising Bridge Superstructures . . . Per Lump Sum	2,000	00	2,000	00
30	For Maintaining Highway Traffic . . . Per Lump Sum	2,000	00	2,000	00
31	3	Store Houses Each	800	00	2,400	00
32	2	Office Buildings Each	250	00	500	00
33	Coffer-dams, Pumping, Bailing and Draining Per Lump Sum	25,000	00	25,000	00
		Total			1,175,623	00

+VV

CONTRACT NO. 68 Champlain CANAL, SECTION 1
 PRELIMINARY ESTIMATE.

SUMMARY OF QUANTITIES

Page
Reference

		Unit of Meas.	Computed Quantities	Rounded Quantities.
<u>Embankment (Wet).</u>				
N-1	Prism near Lock No. 4.	Cu. Yd.	28795	30000
<u>Embankment (Dry)</u>				
E-1	Lock No. 4	Cu. Yd.	2754	2850
FA	Upper Guide Wall- Lock No. 4	" "	4205	4350
K-1	Lock No. 5.	" "	6736	7000
L-1	Upper Guide Wall Lock No. 5	" "	13512	14000
M-1	Prism near Lock No. 4	" "	5835	6050
N-1	" " " " 5	" "	5759	6000
	Bridge department.	" "	2650	2750
			41451	43000
<u>Lining</u>				
	Bridge Department.	Cu. Yd.	465	510
<u>Sawed Lumber (Y.P. or D.F.)</u>				
	Bridge Department.	M.F.B.M.	5	5.6
<u>Sawed Lumber (Y.P. or D.F.) in Needles.</u>				
	Bridge Department.	M.F.B.M.		14
<u>Sawed Lumber (W.O.) in Sills and Gates.</u>				
B-A	Lock No. 3.	M.F.B.M.	1.251	1.3
E-1	" " 4	" " "	1.251	1.3
K-1	" " 5	" " "	1.251	1.3
	Bridge Department.	" " "	20.	21.1
			23.75	25.0
<u>Foundation Piles.</u>				
K-1	Lock No. 5.	Lin. Ft.	780	870
L-1	Upper Guide Wall- Lock No. 5.	" "	1920	2130
			2700	3000

Computed by
Checked by

B. J. Bourne

CONTRACT NO. 68 Champlain CANAL, SECTION 1

PRELIMINARY ESTIMATE.

SUMMARY OF QUANTITIES

Page
ReferenceUnit
of
Meas. Computed
Quantities Rounded
Quantities.Second Class Concrete

A-1	Lower Guide Wall - Lock No. 3	Cu. Yd.	1316	1440
B-A	Lock No. 3	" "	17000	18600
C-1	Upper Guide Wall - Lock No. 3	" "	2919	3200
D-1	Lower " " " No. 4	" "	1323	1440
E-1	Lock No. 4	" "	13235	14500
F-A	Upper Guide Wall - Lock No. 4	" "	1143	1250
G-1	Dam between Perry & Bulson's Ids.	" "	1961	2150
H-1	Lower Guide Wall - Lock No. 5	" "	1788	1960
K-1	Lock No. 5	" "	18902 (19422)	21260
L-1	Upper Guide Wall - Lock No. 5	" "	1629	1780
	Bridge Department	" "	386	420
			62122	68000
			61602	

Reinforced Concrete

B-A	Lock No. 3	Cu. Yd.	370	400
E-1	Lock No. 4	" "	370	400
K-1	Lock No. 5	" "	584 (593)	630
	Bridge Department	" "	60	70
			1393	1500
			1384	

First Class Masonry Coping
Bridge DepartmentCu. Yd. 5Wash-wall

M-1	Prism near Lock No. 4	Cu. Yd.	454	250
N-1	" " " No. 5	" "	3266	1750
			3720	2000

Third Class Stone Paving
Bridge DepartmentSq. Yd. 62 72Fourth Class Rip-rap
For Contingencies (D. A. Watt)Cu. Yd. 200Computed by W. A. L.

CONTRACT NO. 68 Champlain CANAL, SECTION 1

PRELIMINARY ESTIMATE.

SUMMARY OF QUANTITIES

Page
ReferenceUnit
of
Meas Computed
Quantities Rounded
QuantitiesStructural Steel.

A-1	Lower Guide Wall - Lock N ^o . 3.	Lbs.	131	160
B-A	Lock N ^o . 3	"	8936	10600
C-1	Upper Guide Wall - Lock N ^o . 3	"	118	140
D-1	Lower " " " 4	"	288	350
E-1	Lock N ^o . 4.	"	7433	8840
F-A	Upper Guide Wall - Lock N ^o . 4	"	99	120
H-1	Lower " " " 5	"	157	190
K-1	Lock N ^o . 5	"	8825 (7878)	9360
L-1	Upper Guide Wall Lock N ^o . 5	"	198	240
	Bridge Department.	"		150000
				<u>180000</u>

Metal Reinforcement.

A-1	Lower Guide Wall - Lock N ^o . 3.	Lbs.	1203	1450
B-A	Lock N ^o . 3	"	9451	11300
C-1	Upper Guide Wall Lock No. 3	"	3610	4300
D-1	Lower " " " 4	"	2380	2850
E-1	Lock N ^o . 4.	"	8857	10600
F-A	Upper Guide Wall Lock N ^o . 4.	"	833	1000
K-1	Lock N ^o . 5	"	2327 (18770)	22500
	Bridge Department.			7000
				<u>61000</u>

Iron Casting (Plain)

A-1	Lower Guide Wall - Lock N ^o . 3	Lbs.	1500	1670
B-A	Lock N ^o . 3	"	2700	3000
C-1	Upper Guide Wall - Lock N ^o . 3	"	1500	1670
D-1	Lower " " " 4	"	2400	2660
E-1	Lock N ^o . 4	"	3900	4340
F-A	Upper Guide Wall - Lock N ^o . 4	"	6000	6660
H-1	Lower " " " 5	"	1200	1330
K-1	Lock N ^o . 5	"	4200	4670
L-1	Upper Guide Wall Lock N ^o . 5	"	1800	2000
			<u>25200</u>	<u>28000</u>

Computed by

B. J. Construction.

Checked by

CONTRACT NO. 68 Champlain CANAL, SECTION 1
PRELIMINARY ESTIMATE.

SUMMARY OF QUANTITIES

Page
Reference

Unit Meas. Computed Quantities Rounded quantities

Iron Castings (Machined)
Bridge Department

Lbs. 26000

Metal in Lock Gates
Bridge Department

Lbs. 770000

Metal in Buffer Beams
Bridge Department

Lbs. 240000

Metal in Lock Valves
Bridge Department

Lbs. 100000

Wooden Pavement 4" Thick
Bridge Department

Sq.Yd. 360

Wooden Fence
Bridge Department

Lin.Ft. 1050 1150

Drilling Bolt Holes in Rock

C-1

Upper Guide Wall Lock No. 3

Lin.Ft. 630 700

D-1

Lower " " " " 4

" " 400 440

F-A

Upper " " " " 5

" " 140 160

1170 1300

Contract files also contain more detailed estimates, along with schematic drawings, for individual parts of the contract. These sheets demonstrate how needed quantities of concrete and other materials were estimated for construction of the upper guide wall at Lock 4.

CONTRACT No. 68 Champlain CANAL, SECTION 1
PRELIMINARY ESTIMATE.

2nd Class Concrete

Lock #4

FACTORS


Sta.

Area

Dist.

Cu. Ft.

Cu. Yds.

E. Upper Thrust Wall Etc.El. 89.6 - 69.5

$$4.0 \times 39.0 =$$

1560 20.1 3,136

El. 89.6 - 71.5

$$9.0 + 8.0 \times 5.0 =$$

42.5

$$\frac{1.0 \times 4.0}{2} =$$

2.0

$$\frac{4.0 \times 5.0}{2} =$$

2.5

47.0 18.1 851

El. 89.6 - 75.5

$$5.0 \times 39.0 =$$

195.0

Deduct

47.0

148.0 14.1 2087

El. 80.5 - 71.5

$$5.0 + 14.0 \times 49.5 =$$

470.25

$$\frac{14.0 \times 36.5}{2} =$$

511.0

981.25

Deduct

$$35.5 + 41.5 \times 4.0 =$$

154.0

$$\frac{57.0 + 64.0 \times 5.0}{2} =$$

302.5

456.5

El. 93.5 - 69.5

$$4.0 \times 5.5 =$$

524.75 9.0 4723

22.0 24.0 528

El. 93.5 - 67.5

$$41.84 + 43.30 \times 4.0 =$$

170.28

$$\frac{49.5 \times 4.0}{2} =$$

198.0

368.28 26.0 9575

El. 93.5 - 53.5

$$\frac{16.66 + 15.20 \times 4.0}{2} =$$

63.72

40.0 2549

El. 93.5 - 69.5

$$9.0 \times 14.0 =$$

126.0 24.0 3024

El. 93.5 - 70.5

$$8.5 \times 26.5 =$$

225.25 23.0 5181

El. 93.5 - 71.5

$$1.5 \times 26.5 =$$

39.75

$$\frac{1.5 \times 3.5}{2} =$$

2.63

$$\frac{10.0 \times 3.0}{2} =$$

15.0

57.30 22.0 1262

El. 93.5 - 75.5

$$\frac{10.0 + 6.0 \times 6.0}{2} =$$

48.0

$$6.0 \times 15.5 =$$

93.0

$$\frac{6.0 + 1.0 \times 7.0}{2} =$$

24.5

169.87 18.0 3058

$$4.0 \times 5.5 =$$

22.0

CONTRACT NO. 68 Champlain CANAL, SECTION 1
PRELIMINARY ESTIMATE.

2nd Class Concrete

Lock # 4

FACTORS


Sta.

Area

Dist.


Cu. Ft.

Cu. Yds.

3 - Stairs at Upper Thrust Wall

$$\frac{0.79 + 7.79}{2} \times 3.9 = 16.73 \quad 6.0 \quad 100$$

$$0.557 \Sigma (1 + 2 + \dots + 6) = 11.70 \quad 10.00 \quad 117$$

Stairs at Lower Thrust Wall

$$\frac{0.83 + 24.83}{2} \times 13.1 = 168.07$$

Deduct.

$$\frac{2.0 + 10.25}{2} \times 4.5 = 27.56$$

$$9.4 \times 2.0 = 18.8$$


$$\text{Semicircle } 2.0 \text{ Rad} = 6.28 \quad 52.64$$

Deduct

$$115.43 \quad 115.4 \quad 2.0 \quad 231$$

$$(0.83 + 0.5) \times 13.1 = 17.42$$

$$98.01 \quad 4.0 \quad 392$$

Slab on back of Stairs


$$\frac{2.13 + 8.04}{2} \times 10.75 = 54.9$$

$$6.0 \times 8.04 = 48.24$$



$$102.94 \quad 1.5 \quad 154$$

$$994$$


Computed by C. W. Irish.




Contract 68
Lock-4
Upper Guide Wall
Print - 22



Rear Elevation





Plan



Section

Dam
between
Perry's and Bulson's Island



Made by G.B. Kelley
Checked by

Of particular interest are documents showing the planned dam to close off the channel between Bulson's (Vandenburgh's) Island and Parry's Island.

PRELIMINARY ESTIMATE.

SUMMARY OF QUANTITIES

Page Ref.	Meas.	Item	Computed Quantity	Rounded Quantity	Contr. Price	Amount
<u>Dam between Bulson & Perry Islands.</u>						
G-2.	Cu.Yds.	Excavation	264	280	0.75	210
	Cu.Yds.	Embankment	—	—		
G-3.	Cu.Yds.	Second Class Concrete	1961	2150	6.25	13437 50

Computed by B. J. Lowmuth
 Checked by L. W. Overacker

Equally revealing are records documenting the construction of the new bridge over the Hudson River at Stillwater. This bridge was only replaced in recent years.

5

B. C. Form 85

STATE OF NEW YORK
IMPROVEMENT OF THE ERIE, OSWEGO AND CHAMPLAIN CANALS

BILL OF MATERIAL FOR STEEL AND IRON

CONTRACT No. 68

SHEET NOS. Summary for Estimate of Sub Structure
for Stillwater Bridge.

MEMBER	NUMBER	KIND	SIZE	LENGTH OF ONE PIECE		TOTAL LENGTH		WEIGHT PER FOOT	WEIGHT
				FEET	INCHES	FEET	INCHES		
		Excavation							
✓		Roadway (Appr.)	see P.	10		12			Cbyd
+		S.E. Abutment	" "	10		154			
+		N.W.	" "	11		560			726 cbyd
		Embankment							
✓		Roadway (Appr.)	" "	9		2036			Cbyd
+		Backfilling S.E. Ab.	" "	10		128			
+		" " N.W.	" "	11		478			2642 cbyd
		Lining							
✓		Roadway (Appr.)		9		438			Cbyd
✓		" (Abt.)		7		14			
✓		" (Pav. S.E. Abt.)	" "	7		11			463 cbyd
✓		3 rd Class Paving							62 sq. yds.
✓		S.E. Abutment	" "	7					86 Cbyd
+		2 nd Class Concrete	" "	7					2.1 Cbyd
✓		Coping Stone		7					56 Cbyd
✓		Reinforced Concrete	" "	6					5000 lbs
✓		Reinforcement (Steel)		8					1050 Lin.ft.
✓		Wooden Railing		8					
✓		Asphalt Paint for	4 Joints						

Contract No.68 - Alteration No.2

Under this alteration the East Abutment for the highway bridge at Stillwater is carried down to the prism grade and is anchored to rock face; the posts under the reinforced slab are carried down to rock and the size of the pedestals under the posts is changed. The West Abutment is set on the rock as uncovered and is made thicker, eliminating the reinforced slab and the 3rd class paving.

All the quantities except those for the metal superstructure are affected.

The entire quantity for Wash Wall is taken from the Original Contract and put under this alteration, with the necessary increase.

CONTRACTOR'S ACCOUNT OF LABOR AT LOCK NO. 4 - UNDER EXTRA WORK ORDER
DATED NOV. 15, 1910 - CONTRACT 68

Drilling Bolt Holes for Galvanized Pipe in Valve Well Recess, putting
Pipe in place, placing Pull Boxes in Valve Well Recess and Excavating for
Pipes across floor of Lock, covering with concrete, placing Pull Boxes in
floor of Lock, etc.

1911			\$3.60
March 9.	1 Mechanic @ \$3.60 per day.....		3.20
	1 Carpenter @ \$3.20 per day.....		3.60
March 11.	1 Mechanic @ \$3.60 per day.....		3.20
	1 Carpenter @ \$3.20 per day.....		3.60
March 12.	1 Mechanic @ \$3.60 per day.....		3.20
	1 Carpenter @ \$3.20 per day.....		3.60
March 13.	1 Mechanic @ \$3.60 per day.....		3.20
	1 Carpenter @ \$3.20 per day.....		3.60
March 14.	1 Mechanic @ \$3.60 per day.....		3.20
	1 Carpenter @ \$3.20 per day.....		2.00
	1 Helper @ \$2.00 per day.....		3.60
March 15.	1 Mechanic @ \$3.60 per day.....		3.20
	1 Carpenter @ \$3.20 per day.....		2.00
	1 Helper @ \$2.00 per day.....		3.60
March 16.	1 Mechanic @ \$3.60 per day.....		3.20
	1 Carpenter @ \$3.20 per day.....		2.00
	1 Helper @ \$2.00 per day.....		3.20
March 17.	1 Carpenter @ \$3.20 per day.....		3.20
March 20.	1 Carpenter @ \$3.20 per day.....		2.00
	1 Helper @ \$2.00 per day.....		3.20
March 21.	1 Carpenter @ \$3.20 per day.....		4.00
	2 Helpers @ \$2.00 per day.....		6.40
March 22.	2 Carpenters @ \$3.20 per day.....		3.20
March 23.	1 Carpenter @ \$3.20 per day.....		2.00
	1 Helper @ \$2.00 per day.....		4.80
	3 Laborers @ \$1.60 per day.....		3.20
March 24.	1 Carpenter @ \$3.20 per day.....		2.00
	1 Helper @ \$2.00 per day.....		3.20
March 25.	1 Carpenter @ \$3.20 per day.....		3.20
March 26.	1 Carpenter @ \$3.20 per day.....		2.00
	1 Helper @ \$2.00 per day.....		3.20
March 27.	1 Carpenter @ \$3.20 per day.....		2.00
	1 Helper @ \$2.00 per day.....		3.20
April 1.	1 Carpenter @ \$3.20 per day.....		4.00
	2 Helpers @ \$2.00 per day.....		
		Carried Forward /	\$111.60

Contract files include information on salaries paid to skilled workers and laborers to perform specific tasks.

(Sheet 2)

CONTRACTOR'S ACCOUNT OF LABOR AT LOCK NO. 4 - UNDER EXTRA WORK ORDER

DATED NOV/ 15, 1910 - CONTRACT 68

1911		Brought forward.....	\$ 111.60
April 3.	1 Carpenter @ \$3.20 per day.....		3.20
	1 Helper at \$2.00 per day.....		2.00
	1 Laborer @ \$1.60 per day.....		1.60
April 4.	1 Carpenter @ \$3.20 per day.....		3.20
	1 Laborer @ \$1.60 per day.....		1.60
April 6.	1 Carpenter @ \$3.20 per day.....		3.20
	1 Laborer @ \$1.60 per day.....		1.60
April 7.	2 Carpenters @ \$3.20 per day.....		6.40
April 8.	2 Carpenters @ \$3.20 per day.....		6.40
April 10.	2 Carpenters @ \$3.20 per day.....		6.40
	2 Carts @ \$3.00 per day.....		6.00
April 11.	2 Carpenters @ \$3.20 per day.....		6.40
April 12.	2 Carpenters @ \$3.20 per day.....		6.40
	1 Laborer @ \$1.60 per day.....		1.60
April 13.	1 Carpenter @ \$3.20 per day.....		3.20
	4 Laborers @ \$1.60 per day.....		6.40

Total..... \$ 177.20

STATE OF NEW YORK :
:ss.

COUNTY OF Saratoga :

On this.....10..... day of NOV 1911, before me personally appeared.....John P. Parsons..... to me known, who being by me duly sworn, did declare that the above is a just and accurate statement and that the labor shown therein was duly performed.

(Signature)

.....*John P. Parsons*..... Secretary.
SHANLEY-MORRISSEY,
INCORPORATED.

.....*Guan H. Stalder*.....

Asst. to Division Engineer

I certify that the above account is correct.

W. F. Cales

STATE OF NEW YORK

IMPROVEMENT OF THE ERIE, OSWEGO AND CHAMPLAIN CANALS

PRELIMINARY ESTIMATE OF QUANTITIES AND COST

CONTRACT No. 68

Description: For constructing in the Hudson river, Lock No. 3 at Mechanicville; Lock No. 4 at Stillwater; and Lock No. 5 at Northumberland, together with accompanying land lines and all appertaining construction.

Length about 1.4 miles. Sheets 1 to 65 inclusive.

Chapter 147, Laws of 1903
And Amendatory Laws.

ALBANY, July 14, 1908

EM [O.	QUANTITIES	ITEMS	PRICE		AMOUNT	
			Dolls.	Cts.	Dolls.	Cts.
1	Clearing..... Per Lump Sum	100	00	100	00
2	4,800	Cu. Yds. Grubbing..... Per Cu. Yd.		35	1,680	00
3	550,000	Cu. Yds. Excavation..... Per Cu. Yd.		90	495,000	00
4	50	M. Ft. B. M. Sheeting and Bracing... Per M. Ft. B. M.	50	00	2,500	00
4a	1,000	Lin. Ft. Round Timber Bracing..... Per Lin. Ft.		25	250	00
5	170,000	Sq. Ft. Channeling..... Per Sq. Ft.		18	30,600	00
6	30,000	Cu. Yds. Embankment, wet..... Per Cu. Yd.		05	1,500	00
7	43,000	Cu. Yds. Embankment, dry..... Per Cu. Yd.		12	5,160	00
8	510	Cu. Yds. Lining..... Per Cu. Yd.	1	50	765	00
9	5.6	M. Ft. B. M. Sawed Lumber (Yellow Pine or Douglas Fir)..... Per M. Ft. B. M.	55	00	308	00
10	14	M. Ft. B. M. Sawed Lumber in Needles..... Per M. Ft. B. M.	100	00	1,400	00
11	25	M. Ft. B. M. White Oak Lumber in Miter Sills and Gates..... Per M. Ft. B. M.	100	00	2,500	00
12	3,000	Lin. Ft. Foundation Piles..... Per Lin. Ft.		35	1,050	00
13	68,000	Cu. Yds. Second-class Concrete..... Per Cu. Yd.	7	25	493,000	00
14	1,500	Cu. Yds. Reinforced Concrete..... Per Cu. Yd.	9	00	13,500	00
15	5	Cu. Yds. First-class Masonry Coping..... Per Cu. Yd.	30	00	150	00
16	2,000	Cu. Yds. Wash Wall..... Per Cu. Yd.	2	50	5,000	00
17	72	Sq. Yds. Third-class Stone Paving..... Per Sq. Yd.	1	25	90	00
18	200	Cu. Yds. Fourth-class Rip-rap..... Per Cu. Yd.	2	50	500	00
19	180,000	Lbs. Structural Steel..... Per Lb.		05	9,000	00
20	61,000	Lbs. Metal Reinforcement..... Per Lb.		04	2,440	00
21	28,000	Lbs. Iron Castings, plain..... Per Lb.		035	980	00
22	26,000	Lbs. Iron Castings, machined..... Per Lb.		06	1,560	00
23	770,000	Lbs. Metal in Lock Gates..... Per Lb.		06	46,200	00
24	240,000	Lbs. Metal in Buffer Beams..... Per Lb.		06	14,400	00
25	100,000	Lbs. Metal in Lock Valves..... Per Lb.		12	12,000	00
26	360	Sq. Yds. Wooden Pavement, 4" thick..... Per Sq. Yd.	3	00	1,080	00

PRELIMINARY ESTIMATE.

SUMMARY OF QUANTITIES

Page
ReferenceUnit
of
Meas. Computed
Quantity Rounded
QuantityClearing# 100⁰⁰ 100⁰⁰Grubbing

Page Reference	Description	Unit of Meas.	Computed Quantity	Rounded Quantity
E-1	Lock No. 4	Cu. Yds.	322	360
L-1	Upper Guide Wall Lock No. 5.	" "	633	700
M-1	Prism near Lock No. 4.	" "	1277	1420
N-1	" " " " 5.	" "	2092	2320
			4324	4800

Excavation

Page Reference	Description	Unit of Meas.	Computed Quantity	Rounded Quantity
A-1	Lower Guide Wall Lock No. 3	Cu. Yds.	942	1000
B-A	Lock No. 3	" "	44297	46400
C-1	Upper Guide Wall Lock No. 3	" "	2522	2630
D-1	Lower " " " No. 4.	" "	4510	4700
E-1	Lock No. 4.	" "	34020	35500
F-A	Upper Guide Wall Lock No. 4.	" "	2083	2170
G-1	Dam between Bukson & Perry's Ids.	" "	264	280
H-1	Lower Guide Wall - Lock No. 5	" "	9103	9500
K-1	Lock No. 5	" "	44480	46600
L-1	Upper Guide Wall - Lock No. 5	" "	4264	4450
M-1	Prism near Lock No. 4	" "	232219	242000
N-1	" " " " No. 5	" "	147868	154000
	Bridge Department.	" "	730	770
			527302	550000

Sheeting and Bracing.

From Mr. D.A. Watt

M.Ft.B.M. 50

Round Timber Bracing.

From Mr. D.A. Watt.

Lin. Ft. 1000

Channeling.

Page Reference	Description	Unit of Meas.	Computed Quantity	Rounded Quantity
A-1	Lower Guide Wall Lock No. 3	Sq. Ft.	2016	2180
B-A	Lock No. 3	" "	12180	13100
D-1	Lower Guide Wall - Lock No. 4.	" "	8568	9220
E-1	Lock No. 4	" "	26302	28400
F-A	Upper Guide Wall - Lock No. 4	" "	2876	3100
M-1	Prism near Lock No. 4	" "		

Note: For Bridge Room Estimate see sheets following sheet N9

FINAL ACCOUNT

CHAMPLAIN

CANAL

SECTION 1

CONTRACT No. 68

QUANTITIES	ITEMS	CONTRACT PRICE	AMOUNTS	TOTALS
Amount brought forward				
25	96736 Lbs. Metal in Lock Valves Per Lb.	12	11608 32	
26	360 Sq.Yds. wooden Pavement 4" thick			
	Per Sq.Yd.	3 00	1080 00	
27	960 Lin.Ft. wooden Fence " Lin.Ft.	20	192 00	
28	484 Lin.Ft. Drilling Bolt Holes in Rock			
	Per Lin.Ft.	60	290 40	
30	1 Maintaining Highway Traffic			
	Per Lump Sum	2000 00	2000 00	
31	3 Storehouses			
	Each	800 00	2400 00	
32	2 Office Buildings			
	"	250 00	500 00	
33	1 Coffe-dams, Pumping, Bailing and Draining			
	Per Lump Sum	25000 00	25000 00	
1c	978 Cu.Yds. Taking up and relaying Wash Wall			
	Per Cu.Yd.	1 50	1467 00	949352 86
Deduct				
16.744	M.Ft.B.M. Sheeting and Bracing re-used			
	Per M.Ft.B.M.	20 00	334 88	
1d	1 For Coffe-dams, Pumping, Bailing and Draining not required			
	Per Lump Sum	2850 00	2850 00	3184 88
				946167 98

Approved by resolution of the Canal Board

adopted

Secretary of the Canal Board.

CANAL IMPROVEMENT

DEPARTMENT OF STATE ENGINEER AND SURVEYOR

RESIDENT ENGINEER'S MONTHLY REPORT OF CONTRACT WORK ON RESIDENCY NO. 1.

CONTRACT NO. 72-B James Stewart & Co. Inc., CONTRACTOR, Champlain CANAL

MONTH ENDING September 30th, 1916.

WORK DONE

Drill boat 62 worked from Station 833 to Station 831+20. On September 6th, the contractor began using a drill scow with six tripod drills on it for the shallow drilling from Station 831+ 20 to north end of contract. This drill scow was supplied with steam, water, etc., from drill boat 62. This drill scow was used until September 22nd, when 62 resumed drilling.

Dredge worked during month between Station 820 and Station 846. The excavated material was placed in scows and dumped along Green Island, the dredge then cast material up on island.

Dredge and drill boats worked three shifts.

Excavation for month; 13451 Cubic yards.

Average force; 1st. Shift 64 Men worked 7 days.

2nd " 29 " " 7 "


3rd. " 29 " " 7 "

Percentage of work to date. 66.4

E. R. Taylor
.....
Resident Engineer.

The following selected documents describe one of the supplemental contracts for completing the dredging, which the firm of James Stewart & Co. undertook after Shanley and Morrissey ran into financial difficulties. Contract 72B involved widening the canal prism at the mouth of the Hoosic River. Notice the volume of dirt and rock which required excavation, the detailed description of the work to be performed, and the roster of workers involved in the project.

STATE OF NEW YORK



IMPROVEMENT OF THE

Erie, Oswego and Champlain Canals

Chapter 147, Laws of 1903,
And Amendatory Laws

Champlain Canal

CONTRACT NO. 72-B

Section 1

For widening the canal prism in the Hudson River from the mouth of the Hoosic River to the south end of Green Island.

Length 0.74 mile. Sheets 1 to 3 inclusive.

CONTRACT

STATE OF NEW YORK

IMPROVEMENT OF THE ERIE, OSWEGO AND CHAMPLAIN CANALS

MEMORANDUM OF AGREEMENT

James Stewart & Company, Inc., of New York City,

Made between.....

hereinafter referred to as the "Contractor," and the People of the State of New York, hereinafter referred to as the "State," this 7th day of July

1916, by which the Contractor covenants and agrees to furnish all work, labor and services and material of every kind, and to do and perform each and every act and thing necessary or

proper for the improvement of the Champlain canal,

by widening the canal prism in the Hudson River from the mouth of the Hoosic River to the south end of Green Island, as embraced in Contract No. 72-B, Barge Canal,

.....in accordance with the plans and specifications for said work hereto annexed and forming a part hereof, and to fully complete said improvement in accordance with the true intent and meaning of said plans and specifications without any further, other or different expense of any nature whatsoever to the State, excepting the consideration to be paid therefor by the State, as hereinafter more particularly mentioned.

1. It being understood and agreed that the Contractor shall make said improvements and conduct the work in compliance with all laws of the State of New York and the ordinances of any city, village or town and the lawful directions of the officers, agents or representatives of the State or of said city, village or town.

2. The Contractor further stipulates and agrees pursuant to Section 3, Article II, of the Labor Law, that no laborer, workman or mechanic in the employ of the Contractor, sub-contractor or other person doing or contracting to do the whole or a part of the work contemplated by this contract, shall be permitted or required to work more than eight hours in any one calendar day, except in case of extraordinary emergency caused by fire, flood or danger to life or property.

3. The Contractor further stipulates and agrees that the wages to be paid for a legal day's work as hereinbefore defined, to all classes of such laborers, workmen or mechanics employed by him or by any sub-contractor or other person on, about or upon said work or upon any material to be used upon or in connection therewith, shall not be less than the prevailing rate of wages for a day's work in the same trade or occupation in the locality within the State where such public

FAITHFUL PERFORMANCE BOND

KNOW ALL MEN BY THESE PRESENTS

That we James Stewart & Co., Inc., of New York City
Contractor and National Surety Company, a Corporation under the
Laws of the State of New York

surety are held and jointly and
severally firmly bound unto THE PEOPLE OF THE STATE OF NEW YORK in the sum of
Ten thousand , eight hundred and fifty-four dollars

(\$ 10,854.00) lawful money of the United States, to be paid to the said, the People of the
State of New York or to their certain attorney or attorneys or assigns, for which payment,
well and truly to be made, we bind ourselves, our successors, heirs, executors, administrators and
assigns, jointly and severally, firmly by these presents.

SEALED with our seals. Dated this 7th day of July

In the year of our Lord one thousand nine hundred and sixteen

WHEREAS the above bounden Contractor has covenanted and agreed to furnish all work,
labor and services and material of every kind, and to do and perform each and every act and thing
necessary and proper for the improvement of the canal by widening the canal prism
in the Hudson River from the mouth of the Hoosic River to the

south end of Green Island, as embraced in Contract No. 72-B,

Barge Canal,

in accordance with the plans and specifications for said work adopted by the Canal Board of the
State of New York, or in accordance with said plans and specifications as the same may be altered
by the proper officers or agents of the State of New York from time to time.

THE CONDITION OF THIS OBLIGATION IS SUCH that if the said Contractor.....,
~~his, its, their~~ successors, executors, administrators, or assigns, or either of them shall faithfully
and completely perform said contract, then this obligation to be void, otherwise to remain in full
force and effect. The said surety hereby stipulates and agrees that no change, extension, alter-
ation or revision of the terms of said contract or of the plans and specifications accompanying
the same shall in any way affect ~~his, their, its~~ obligation on this bond.

(Seal)

James Stewart & Company, Inc., (Seal)

Per A. M. Stewart, President (Seal)

National Surety Company (Seal)

by Howard Abrahams Vice President

CONTRACT NO. 72-B Champlain CANAL, SECTION 1Widening PrismPreliminary

ESTIMATE.

Excavation

Cross Sec. Bk. Pg.	Sta.	Length of Section	Area	Cu. Ft.	Cu. Yds.	Cross Sec. Bk. Pg.	Sta.	Length of Section	Area	Cu. Ft.	Cu. Yds.
-----------------------	------	----------------------	------	---------	----------	-----------------------	------	----------------------	------	---------	----------

820+00			0								
821+00	100		264	13200							
822+00	100		550	40700							
823+00	100		700	62500							
824+00	100		700	70000							
825+00	100		700	70000							
827+00	200		695	139500							
829+00	200		645	134000							
831+00	200		590	123500							
833+00	200		600	119000							
835+00	200		590	119000							
837+00	200		500	109000							
839+00	200		538	103800							
841+00	200		490	102800							
843+00	200		425	91500							
845+00	200		400	82500							
847+00	200		465	86500							
849+00	200		300	76500							
851+00	200		300	60000							
853+00	200		275	57500							
855+00	200		250	52500							
857+00	200		150	40000							
859+00	200		16	16600							
859+20	20		0	160							
				1770760							

65584 Cu. Yds.

Computed by TigheCopied by Westall
OverweyChecked by Sparre

CANAL IMPROVEMENT
DEPARTMENT OF STATE ENGINEER AND SURVEYOR. }

RESIDENT ENGINEER'S MONTHLY REPORT OF ENGINEER FORCE ON CONTRACT No. 72B.

RESIDENCY No. 1.

Champlain CANAL

Jas. Stewart & Co., Inc., CONTRACTOR

MONTH ENDING September 30, 191 6.

NAME	RANK	DATES—Inclusive		
		From	To	
W. L. Caler,	Assistant Engineer	1	30	27
N. D. Hyde,	Junior Engineer	1 9	4 30	<u>4</u> <u>22</u> 26
Floyd F. Baker,	Rodman	1	30	28
D. J. Begley,	Chairman	1	30	29
James Sim,	Inspector of Masonry	1	14	12
Willard Joslin,	Boatman	21	30	9
Geo. C. Schafer,	"	1	30	30

MONTHLY ESTIMATE

Champlain CANAL SECTION 1, Eastern DIVISION
 ESTIMATE No. 8 of work done up to April 1, 1917
 by Jas. Stewart & Co., Inc., Contractor, under Contract No. 72B,
 dated July 7, 1916 under Chapter 147, Laws 1903 and Amendatory Laws.

For widening the canal prism in the Hudson river
 from the mouth of the Hoosic river to the south
 end of Green Island. Length, 0.74 mile.

QUANTITIES		ITEMS	CONTRACT PRICE	AMOUNTS	TOTALS
Increase	Total to date				

There has been no increase in the
 quantities of work done on Contract No. 72B
 during March, 1917.

The quantities of the various items
 estimated to April 1, 1917, are the same as in
 Estimate No. 5, dated January 1, 1917. For
 details of present estimate see Estimate No. 5.

In the Summary below is shown the
 total estimate of work done to date.

SUMMARY

Original Contract,	\$90123 84
<u>SAY</u>	\$90120 00

*and
 by contract 4-11-17*

 Special Deputy State Engineer

ENGINEERS' CERTIFICATES TO MONTHLY ESTIMATE

Champlain CANAL, SECTION 1 CONTRACT NO. 72-BSTATE OF NEW YORK
COUNTY OF SaratogaI, W. L. Caler

Assistant Engineer of the Department of the State Engineer and Surveyor, hereby certify

under oath, that to the best of my knowledge and belief, there is now due by the State to Jas. Stewart & Co., Inc.
Contractors, Eight Thousand Five Hundred fifty-nine and 00/100 (\$8559.00) dollars for work done and
not before included in any estimate, up to the 1st day of November 1916, under Contract No. 72-B
dated July 7, 1916, on the Eastern Division Champlain CanalFor widening the canal prism in the Hudson River from the mouth of the
Hoosic River to the south end of Green Island. Length 0.74 miles.

and I further certify that the said amount has been estimated from actual measurements and inspections by me made, as Assistant Engineer, of all work done and not included in the last previous estimate and of all work done during my official connection with the said contract, and from the official notes of measurements made by my predecessors of work done under them, and believe it to be correct and in strict accordance with the terms of the contract.

Subscribed and sworn before me this 4th
day of November 1916W. L. Caler Assistant Engineer

Asst. to Division Engineer

I, E. V. R. Payne Resident Engineer on that portion of the canals embracing Contract
No. 72-B, above specified, hereby certify that I have caused careful measurements to be made by my sworn assistants, as far as practicablesupervised the same, and from time to time have made personal inspections of the work done under said contract, up to the 1st
day of November 1916, and from the facts thus obtained have made an estimate of the cost thereof with reference to the
prices contained in the contract; and that the amount of the work done, up to the date aforesaid, not before included in any estimate, according to such estimate amounts to
the sum of Nine Thousand Five Hundred ten and 00/100 (\$9510.00) dollars.And which amount I believe does not exceed the actual quantities and value of the amount of work done by the aforesaid contractors, in strict accordance with the terms
of the said contract.Dated November 4, 1916.E. V. R. Payne Resident EngineerI, Geo. D. Williams

Division Engineer of the Department of the State Engineer and Surveyor, hereby certify

that I have carefully examined the estimate referred to in the above certificates, and as far as practicable examined the work covered by it, and believe it to be correct and in
strict accordance with the contract.Dated Nov 5 1916Geo. D. Williams Division Engineer

EXAMINED AND APPROVED

NOV 1916

Special Deputy State Engineer

Series # B1009. New York State Barge Canal plans, 1920. .1 cu. ft. (1 volume containing 156 plates) Indexes: A list of plates in front of volume functions as an index.

These plates of plans, drawings, profiles and location maps relate to the improvement and enlargement of the Barge Canal. The volume was issued as a supplement to the State Engineer and Surveyor's 1920 annual report with the express intent to preserve the work of the engineers involved, to "be of lasting benefit to the engineering profession" and to assist in the design of future public or private works.

The plates show typical work done as well as some features special or unique to the Barge Canal project. Two examples of unique engineering problems documented are Cohoes Falls, which resulted in the greatest series of high lift locks then known in the world; and the gorge near Medina at Oak Orchard Creek, which required an unusually high channel and walls bordering the gorge--after plans for the largest (at that time) single span concrete structure ever devised were given up. Since locks and dams were the most important structures in the project they, along with bridges, are most frequently represented in the volume.

Generally the plates depict the following structures: typical channel sections, prism walls and other types of wall and bank protection employed; locks; power plants; fixed and movable dams (including a dam with automatic crest that originated in the course of designing the canal); guard gates; siphon spillways (which also originated with barge canal design, providing automatic starting and stopping of the flow of water); culverts and aqueducts (notably the largest one in the barge system, which did not have the long aqueducts found in the old canal system); bridges (flat, bascule, and steel arch types); terminal piers and dockwalls; and navigation aids (lighthouse buoys, tankhouses, etc.). The few maps found in the volume are strictly for location and are placed within the larger general plan.

The plans reproduced here are generic to many Barge Canal locks, including Champlain Lock. They include overview of buildings or large sections of the lock, as well as details of gate construction, a hydroelectric generator, pile foundations and electric circuitry.

SIZES OF POWER-HOUSES

The power-houses built very in size to suit the local conditions and machinery used. Sizes built at the various locks where vertical shaft generators directly connected to hydraulic turbines are employed.

Canal Lock	Canal	Floor Space	Floor Spm.	Canal Lock	Canal	Floor Space	Floor Spm.
Erie 1	91	20.5' x 40.0'	82	20.0' x 40.0'	92	20.0' x 40.0'	82
Erie 2	92	14.5' x 26.6'	2	14.0' x 40.0'	93	14.0' x 40.0'	2
Erie 3	93	16.0' x 23.7'	3	20.0' x 40.0'	94	20.0' x 40.0'	3
Erie 4	94	20.0' x 33.0'	4	20.0' x 40.0'	95	20.0' x 40.0'	4
Erie 5	95	20.0' x 33.0'	5	20.0' x 40.0'	96	20.0' x 40.0'	5
Erie 6	96	20.0' x 33.0'	6	20.0' x 40.0'	97	20.0' x 40.0'	6
Erie 7	97	16.0' x 24.6'	7	20.0' x 40.0'	98	20.0' x 40.0'	7
Erie 8	98	16.0' x 24.6'	8	20.0' x 40.0'	99	20.0' x 40.0'	8
Erie 9	99	16.0' x 24.6'	9	20.0' x 40.0'	100	20.0' x 40.0'	10
Erie 10	100	16.0' x 24.6'	10	20.0' x 40.0'	101	20.0' x 40.0'	11
Erie 11	101	16.0' x 24.6'	11	20.0' x 40.0'	102	20.0' x 40.0'	12
Erie 12	102	16.0' x 24.6'	12	20.0' x 40.0'	103	20.0' x 40.0'	13
Erie 13	103	16.0' x 24.6'	13	20.0' x 40.0'	104	20.0' x 40.0'	14
Erie 14	104	16.0' x 24.6'	14	20.0' x 40.0'	105	20.0' x 40.0'	15
Erie 15	105	16.0' x 24.6'	15	20.0' x 40.0'	106	20.0' x 40.0'	16
Erie 16	106	16.0' x 24.6'	16	20.0' x 40.0'	107	20.0' x 40.0'	17
Erie 17	107	16.0' x 24.6'	17	20.0' x 40.0'	108	20.0' x 40.0'	18
Erie 18	108	16.0' x 24.6'	18	20.0' x 40.0'	109	20.0' x 40.0'	19
Erie 19	109	16.0' x 24.6'	19	20.0' x 40.0'	110	20.0' x 40.0'	20
Erie 20	110	16.0' x 24.6'	20	20.0' x 40.0'	111	20.0' x 40.0'	21
Erie 21	111	16.0' x 24.6'	21	20.0' x 40.0'	112	20.0' x 40.0'	22
Erie 22	112	16.0' x 24.6'	22	20.0' x 40.0'	113	20.0' x 40.0'	23
Erie 23	113	16.0' x 24.6'	23	20.0' x 40.0'	114	20.0' x 40.0'	24
Erie 24	114	16.0' x 24.6'	24	20.0' x 40.0'	115	20.0' x 40.0'	25
Erie 25	115	16.0' x 24.6'	25	20.0' x 40.0'	116	20.0' x 40.0'	26
Erie 26	116	16.0' x 24.6'	26	20.0' x 40.0'	117	20.0' x 40.0'	27
Erie 27	117	16.0' x 24.6'	27	20.0' x 40.0'	118	20.0' x 40.0'	28
Erie 28	118	16.0' x 24.6'	28	20.0' x 40.0'	119	20.0' x 40.0'	29
Erie 29	119	16.0' x 24.6'	29	20.0' x 40.0'	120	20.0' x 40.0'	30
Erie 30	120	16.0' x 24.6'	30	20.0' x 40.0'	121	20.0' x 40.0'	31
Erie 31	121	16.0' x 24.6'	31	20.0' x 40.0'	122	20.0' x 40.0'	32
Erie 32	122	16.0' x 24.6'	32	20.0' x 40.0'	123	20.0' x 40.0'	33
Erie 33	123	16.0' x 24.6'	33	20.0' x 40.0'	124	20.0' x 40.0'	34
Erie 34	124	16.0' x 24.6'	34	20.0' x 40.0'	125	20.0' x 40.0'	35
Erie 35	125	16.0' x 24.6'	35	20.0' x 40.0'	126	20.0' x 40.0'	36
Erie 36	126	16.0' x 24.6'	36	20.0' x 40.0'	127	20.0' x 40.0'	37
Erie 37	127	16.0' x 24.6'	37	20.0' x 40.0'	128	20.0' x 40.0'	38
Erie 38	128	16.0' x 24.6'	38	20.0' x 40.0'	129	20.0' x 40.0'	39
Erie 39	129	16.0' x 24.6'	39	20.0' x 40.0'	130	20.0' x 40.0'	40
Erie 40	130	16.0' x 24.6'	40	20.0' x 40.0'	131	20.0' x 40.0'	41
Erie 41	131	16.0' x 24.6'	41	20.0' x 40.0'	132	20.0' x 40.0'	42
Erie 42	132	16.0' x 24.6'	42	20.0' x 40.0'	133	20.0' x 40.0'	43
Erie 43	133	16.0' x 24.6'	43	20.0' x 40.0'	134	20.0' x 40.0'	44
Erie 44	134	16.0' x 24.6'	44	20.0' x 40.0'	135	20.0' x 40.0'	45
Erie 45	135	16.0' x 24.6'	45	20.0' x 40.0'	136	20.0' x 40.0'	46
Erie 46	136	16.0' x 24.6'	46	20.0' x 40.0'	137	20.0' x 40.0'	47
Erie 47	137	16.0' x 24.6'	47	20.0' x 40.0'	138	20.0' x 40.0'	48
Erie 48	138	16.0' x 24.6'	48	20.0' x 40.0'	139	20.0' x 40.0'	49
Erie 49	139	16.0' x 24.6'	49	20.0' x 40.0'	140	20.0' x 40.0'	50
Erie 50	140	16.0' x 24.6'	50	20.0' x 40.0'	141	20.0' x 40.0'	51
Erie 51	141	16.0' x 24.6'	51	20.0' x 40.0'	142	20.0' x 40.0'	52
Erie 52	142	16.0' x 24.6'	52	20.0' x 40.0'	143	20.0' x 40.0'	53
Erie 53	143	16.0' x 24.6'	53	20.0' x 40.0'	144	20.0' x 40.0'	54
Erie 54	144	16.0' x 24.6'	54	20.0' x 40.0'	145	20.0' x 40.0'	55
Erie 55	145	16.0' x 24.6'	55	20.0' x 40.0'	146	20.0' x 40.0'	56
Erie 56	146	16.0' x 24.6'	56	20.0' x 40.0'	147	20.0' x 40.0'	57
Erie 57	147	16.0' x 24.6'	57	20.0' x 40.0'	148	20.0' x 40.0'	58
Erie 58	148	16.0' x 24.6'	58	20.0' x 40.0'	149	20.0' x 40.0'	59
Erie 59	149	16.0' x 24.6'	59	20.0' x 40.0'	150	20.0' x 40.0'	60
Erie 60	150	16.0' x 24.6'	60	20.0' x 40.0'	151	20.0' x 40.0'	61
Erie 61	151	16.0' x 24.6'	61	20.0' x 40.0'	152	20.0' x 40.0'	62
Erie 62	152	16.0' x 24.6'	62	20.0' x 40.0'	153	20.0' x 40.0'	63
Erie 63	153	16.0' x 24.6'	63	20.0' x 40.0'	154	20.0' x 40.0'	64
Erie 64	154	16.0' x 24.6'	64	20.0' x 40.0'	155	20.0' x 40.0'	65
Erie 65	155	16.0' x 24.6'	65	20.0' x 40.0'	156	20.0' x 40.0'	66
Erie 66	156	16.0' x 24.6'	66	20.0' x 40.0'	157	20.0' x 40.0'	67
Erie 67	157	16.0' x 24.6'	67	20.0' x 40.0'	158	20.0' x 40.0'	68
Erie 68	158	16.0' x 24.6'	68	20.0' x 40.0'	159	20.0' x 40.0'	69
Erie 69	159	16.0' x 24.6'	69	20.0' x 40.0'	160	20.0' x 40.0'	70
Erie 70	160	16.0' x 24.6'	70	20.0' x 40.0'	161	20.0' x 40.0'	71
Erie 71	161	16.0' x 24.6'	71	20.0' x 40.0'	162	20.0' x 40.0'	72
Erie 72	162	16.0' x 24.6'	72	20.0' x 40.0'	163	20.0' x 40.0'	73
Erie 73	163	16.0' x 24.6'	73	20.0' x 40.0'	164	20.0' x 40.0'	74
Erie 74	164	16.0' x 24.6'	74	20.0' x 40.0'	165	20.0' x 40.0'	75
Erie 75	165	16.0' x 24.6'	75	20.0' x 40.0'	166	20.0' x 40.0'	76
Erie 76	166	16.0' x 24.6'	76	20.0' x 40.0'	167	20.0' x 40.0'	77
Erie 77	167	16.0' x 24.6'	77	20.0' x 40.0'	168	20.0' x 40.0'	78
Erie 78	168	16.0' x 24.6'	78	20.0' x 40.0'	169	20.0' x 40.0'	79
Erie 79	169	16.0' x 24.6'	79	20.0' x 40.0'	170	20.0' x 40.0'	80
Erie 80	170	16.0' x 24.6'	80	20.0' x 40.0'	171	20.0' x 40.0'	81
Erie 81	171	16.0' x 24.6'	81	20.0' x 40.0'	172	20.0' x 40.0'	82
Erie 82	172	16.0' x 24.6'	82	20.0' x 40.0'	173	20.0' x 40.0'	83
Erie 83	173	16.0' x 24.6'	83	20.0' x 40.0'	174	20.0' x 40.0'	84
Erie 84	174	16.0' x 24.6'	84	20.0' x 40.0'	175	20.0' x 40.0'	85
Erie 85	175	16.0' x 24.6'	85	20.0' x 40.0'	176	20.0' x 40.0'	86
Erie 86	176	16.0' x 24.6'	86	20.0' x 40.0'	177	20.0' x 40.0'	87
Erie 87	177	16.0' x 24.6'	87	20.0' x 40.0'	178	20.0' x 40.0'	88
Erie 88	178	16.0' x 24.6'	88	20.0' x 40.0'	179	20.0' x 40.0'	89
Erie 89	179	16.0' x 24.6'	89	20.0' x 40.0'	180	20.0' x 40.0'	90
Erie 90	180	16.0' x 24.6'	90	20.0' x 40.0'	181	20.0' x 40.0'	91
Erie 91	181	16.0' x 24.6'	91	20.0' x 40.0'	182	20.0' x 40.0'	92
Erie 92	182	16.0' x 24.6'	92	20.0' x 40.0'	183	20.0' x 40.0'	93
Erie 93	183	16.0' x 24.6'	93	20.0' x 40.0'	184	20.0' x 40.0'	94
Erie 94	184	16.0' x 24.6'	94	20.0' x 40.0'	185	20.0' x 40.0'	95
Erie 95	185	16.0' x 24.6'	95	20.0' x 40.0'	186	20.0' x 40.0'	96
Erie 96	186	16.0' x 24.6'	96	20.0' x 40.0'	187	20.0' x 40.0'	97
Erie 97	187	16.0' x 24.6'	97	20.0' x 40.0'	188	20.0' x 40.0'	98
Erie 98	188	16.0' x 24.6'	98	20.0' x 40.0'	189	20.0' x 40.0'	99
Erie 99	189	16.0' x 24.6'	99	20.0' x 40.0'	190	20.0' x 40.0'	100
Erie 100	190	16.0' x 24.6'	100	20.0' x 40.0'	191	20.0' x 40.0'	101
Erie 101	191	16.0' x 24.6'	101	20.0' x 40.0'	192	20.0' x 40.0'	102
Erie 102	192	16.0' x 24.6'	102	20.0' x 40.0'	193	20.0' x 40.0'	103
Erie 103	193	16.0' x 24.6'	103	20.0' x 40.0'	194	20.0' x 40.0'	104
Erie 104	194	16.0' x 24.6'	104	20.0' x 40.0'	195	20.0' x 40.0'	105
Erie 105	195	16.0' x 24.6'	105	20.0' x 40.0'	196	20.0' x 40.0'	106
Erie 106	196	16.0' x 24.6'	106	20.0' x 40.0'	197	20.0' x 40.0'	107
Erie 107	197	16.0' x 24.6'	107	20.0' x 40.0'	198	20.0' x 40.0'	108
Erie 108	198	16.0' x 24.6'	108	20.0' x 40.0'	199	20.0' x 40.0'	109
Erie 109	199	16.0' x 24.6'	109	20.0' x 40.0'	200	20.0' x 40.0'	110

W. H. Crescent/ dem.

Four houses have been built for hydroelectric power generation. The first three are of the same size and are built on the same site. The fourth is of a different size and is built on a different site. The following table shows the sizes of these houses.

Three houses have been built for sub-stations. Two for the Niagara Falls and one for the Buffalo. The first two are of the same size and are built on the same site. The third is of a different size and is built on a different site. The following table shows the sizes of these houses.


Eleven houses have been built for gas-electric stations. All have the same size and are built on the same site. The following table shows the sizes of these houses.

These houses are all 20'-0" x 30'-0" inside of floor level.


All concrete on this sheet to be first-class reinforced concrete. All edges to be rounded to a radius of 1" unless otherwise noted. Walls to be of masonry construction.

NEW YORK STATE BARGE CANAL Department of State Engineer and Surveyor TYPICAL HYDRO-ELECTRIC POWER-PLANT GENERAL PLAN OF BUILDING


Scale: 1/4" = 1'-0" feet
except as noted




NW END ELEVATION




SIDE ELEVATION



SE END ELEVATION



PLAN




TRANSVERSE SECTION



ROOF PLAN



SECTION D-D




DEVELOPMENT OF INNER WALL SURFACES SHOWING IMBEDDED STEEL CONDUIT


- V. Outlet of lamp bracket
- H. Outlet of heater
- J. Outlet of portable lamp
- K. Junction for lighting circuit
- L. Wire for lighting circuit
- M. Wire for heater circuit


WOODEN LOCK-GATE PLANS
DETAIL PLANS OF UPPER GATES

CONTRACT G. SHEET NO.



See Sheet 9 for details of built-up timbers. This sheet shows an alternate detail using single timbers. The slide reserves the right to discontinue the use of timbers in sizes not over 12" x 12". See Specifications para. 2.1. The vertical dimension of each timber may be varied subject to the approval of the Engineer and as shown on the detail drawings to be submitted by the Contractor for approval.





NEW YORK STATE BARGE CANAL
Department of State Engineer and Surveyor

TYPICAL GASOLINE-ELECTRIC POWER-PLANT
ASSEMBLY OF ENGINE AND GENERATOR

CONTRACTS NOS. 92, 93 & 94, SHOP DRAWINGS

Series # 11833. Barge Canal construction photographs, 1905-1921. 21.3 cu. ft.

These photographs appear to have been submitted to the State Engineer and Surveyor by the Board of Consulting Engineers, a board of five civil engineers appointed to follow the progress of work on the canal system and to report on it to the State Engineer and Surveyor. Photographs were taken at the end of each month just before monthly cost estimates of work to be done were made.

Photographs show canals; locks; dams; bridges; piers; nearby buildings; damages needing repair; and dredging, excavation, repairs, and construction work in progress. Included are photographs of Barge Canal terminal structures in Buffalo. Captions typed or written on most photographs provide date of photograph; negative number; contract number; and location. Series B0727 (page 39) contains related glass plate negatives of western division Barge Canal construction.

The first three photos, taken on November 24, 1909, show the prism excavation in its early stages. Note the steam locomotive in use on a temporary railroad in removal of tons of crushed shale rock.

at 84 Cent 74 Showing rock excavation from canal prism (north end)

Stillwater Nov. 24-09 +



Box 80 Cont 68 South end of cut showing rock site

Stillwater

Nov. 24-09



68 Cont 68 Showing rock excavation from canal prism
(north end of cut looking south)

Stillwater

Nov. 24-09



Showing rock excavation from canal prism

Nov. 24-09

Four photos taken on May 11, 1910 show that additional progress has been made. Note the steam-powered cranes and shovels, and the early concrete mixer. The rock was removed both by machine and manual labor. The Kipp house shows in the background of the first photo, which looks north. Work on the abutments of the new Stillwater Bridge was just under way.

Neg. 100 Contract 68
Showing progress of lock excavation,
May 11-10


Stillwater.




Reg. 1403 Contract 72
Progress of excavation, Stillwater. May 11-10



1968, 103 Contract 88
Concrete mixer at Stillwater
May 11-10




Neg. 101 Contract No. 68
Showing forms for east bridge abutment Stillwater
May 11-10




By the time the next five photos were taken on June 30th, work had progressed significantly. The first photo shows a steam shovel working on the prism south of the lock; the view looks west between Green and Parry's islands towards Stillwater. The next three photos show construction of the lock progressing, including a finished guide wall. In the final photo, the eastern abutment of the bridge to Stillwater is nearly completed.


Res. 1404 Contract 72
Showing progress of cut at Stillwater. June 30-10



Neg. 117 Contract 68
Progress of Lock 4 at Stillwater.
June 30-10




Neg. 118 Contract 88
Progress of Lock & Stillwater.
June 30, 1910.



Neg. 116 contract 68
Showing guide wall for Lock 4 at Stillwater.
June 30--10




115 Contract 68
Bridge abutment (front view) at Stillwater
June 30-10



Photos taken on July 28th show the actual lock beginning to take shape, as well as a cofferdam at the mouth of the Hoosic River, where dredging was taking place.

Contract 88
Progress of Lock 4
July 28-10



Contract as
progress of work at Philadelphia.



NEG. 1409 Contract 72
Coferdam at mouth of Hoosick river, Mechanicville.
July 28-10



The first August 29 photo shows the excavation at the confluence of the rivers, showing Green Island and the Boston and Maine Railroad bridge in the distance. The guide and lock walls are now closer to completion.

112. 1000 ft. deep

113. 1000 ft. deep excavation showing well developed

114. 1000 ft. deep



Contract 68
Showing construction of guide wells, Stillwater.
Aug. 29-10





FIG. 136 Contract 68
Sections of lock and guide wall, Stillwater.
Aug. 1910




Neg. 144 Cont. on 88
Showing ground of Lock 4-83



Four photos taken on October 31 show the actual lock construction progressing well.


Neg. 145. Contract 68
Showing progress of Lock 4, Stillwater. Oct. 31-10



Neg. 146 Contract 68
Showing progress of Lock 4 Stillwater
Oct. 31-10



Neg. 147 Contract 68
Showing progress of Lock 4 at Stillwater
Oct. 31-10



The first photo taken on January 30, 1911 shows a cofferdam to keep water from entering the south end of the lock. One span of the new steel highway bridge is now in place at this time, and work is beginning on the lock superstructure.

Neg. 152 Contract 38
Cofferdam south end of Lock 4, Stillwater.
Jan. 30-11




Neg. 154 Contract 68
General view of Lock 4.
Jan. 30-11

Stillwater.




By the time these five photos were taken on May 24th, the lock was nearing completion. The huge doors were in place and final work was being done on the superstructure and the adjacent prisms.

NOZ. 159 Contract 68
Progress of Lock 4, looking south, Stillwater, N. Y.
May 24-11



Neg. 130 Contract 68
Showing approach wall, Lock 4, looking south, Stillwater, N. H.
May 24-11



Neg. 181


Contract 68

SHOWING prism north of Lock 4, looking south, Stillwater, N. Y.


May 24-11




Neg. 182 Contract 68
Showing gates and needle beam in place, Lock No. 4, looking south
Stillwater, N. Y. May 24-11



Nec. 182 Contract 88
showing chamber of Lock 4, looking north, Stillwater, N. Y.
May 24-11



LOCK 100 Contract 38
LOCK 9, Stillwater, June 4-19



Work has been completed when the final photos were taken on June 24th, 1912. The first view looks east and shows the generating building which has been erected. The remains of the former Dwaas Kill are visible to the left. In the final view, looking towards the new Stillwater bridge and the old Kipp house, not yet demolished, canoeists enjoy the flat water in the canal prism.

Contract 68
Lock and Canal north of Lock 4, Stillwater.
June 4-12



Other Barge Canal Records Held By the New York State Archives

The New York State Archives holds series of records relating to New York State's Barge Canal that are not reproduced in this publication. Of these records, the following series are recommended for the information they contain relative to the canal's development and actual construction:

Series # B0253. Barge Canal sectional maps ("Schillner Maps"), ca. 1896. ca. 132 cu. ft. (71 maps) Arrangement: By location.

This series consists of 71 manuscript maps depicting land along the Erie, Champlain, and Oswego canals acquired by the State for canal purposes up to 1896. The maps are apparently the product of surveys conducted by the office of the State Engineer and Surveyor in response to Chapter 79 of the Laws of 1895, which appropriated nine million dollars for the improvement of the canals. These maps contain only selected information from the even more detailed surveys (see series B0396, page 44). Each sectional map provides detailed information on State-owned property, depicted as the area between two solid blue lines. The maps are especially important because they show, within dotted blue lines, the locations of the 1825 canal alignment and the related structures which had since been obliterated, such as locks, slips, dams, bridges, and roads. In addition they show city, town and county lines; streams, rivers, bodies of water and islands; property lines, along with names of owners and sometimes acreage of land; and streets, railroad lines, businesses and civic landmarks (ice companies, mills, cemeteries, etc.). The maps are commonly referred to as the "Schillner Maps" after George L. Schillner, who apparently supervised their execution in 1896. No scale is given, but figures mark canal frontage and survey measurements by number of chains (1 chain = 66 feet).

Series # A0867. Whiteprint copies of maps of lands permanently appropriated by the State for canal purposes ("blue line maps"), 1917-1948. 28 cu. ft. (69 portfolios containing ca. 850 maps) Arrangement: Geographical by portfolio and therein numerical by map number. Finding aids: A portfolio list provides inclusive map numbers and brief description of canal and geographic area.

This series consists of whiteprint copies of original survey maps, commonly referred to as "blue line maps," of land appropriated by the State for canal purposes. The maps depict in minute detail lands acquired for canal purposes up to and including the time of construction of the Barge Canal. The Department of Public Works (earlier the State Engineer and Surveyor) produced and retained the original maps and submitted whiteprint copies to the Comptroller and Secretary of

State. This set of maps was filed with the Comptroller. Laws of 1910 (Chapter 199) and 1917 (Chapter 51) authorized the production of "blue line maps" (the blue lines indicated boundaries of State-owned lands along the Erie, Champlain, Oswego, Black River, and Cayuga and Seneca canals) to minimize property disputes resulting from the construction of the Barge Canal. The maps depict inner angles of the towpaths on the old canal; property owned by the State prior to Barge Canal construction; property appropriated by the State for the Barge Canal project; locations of the old canal lines; location of the proposed Barge Canal; and various structures, roads, streets, and other landmarks and the names of owners of private property adjacent to the canal.

Series # B0171. Maps, blueprints, tracings, drawings, plans, and cross sections of canal structures and sites, ca. 1830-1947. 250 items Arrangement: None.

These records primarily concern the Barge Canal system and its feeders. There are also items depicting the old Erie Canal and lesser canals such as the Black River Canal. The majority of maps depict various canal structures such as bridges, diversion channels, dams, sewers, locks, culverts, stop gates, and aqueducts. The remaining records show land patents, locations of towns and villages, land claims, towpath locations, and streets in cities where canals were situated.

Series # A1277. Notices of service upon owners of lands appropriated for the Barge Canal, 1906-1916. .8 cu. ft. (3 volumes)

Series # B0338. Depositions regarding notices of land appropriations for Barge Canal purposes, 1913-1916. .3 cu. ft. (1 volume) Arrangement: Chronological by date of deposition.


Three volumes contain carbon copies of affidavits of annexed notices of appropriations of property by the State. The affidavit is signed by an employee of the Department of Public Works (on behalf of the Superintendent of Public Works) and states that the Department under a law of 1903 has annexed the lands described and is thereby informing the owner of the land in writing as the Department has been unable to reach the owner in person. These affidavits contain detailed descriptions of the land to be appropriated by the State for Barge Canal purposes pursuant to laws of 1903, 1909, and 1911. An insert in the beginning of volume 1905-1911 dated March 13, 1905 entitled "Procedure in taking possession of lands under Chapter 147 of the Laws of 1903" describes in detail the procedures and policies involved.

Series # B0233. Card index to locations of Barge Canal construction records, 1917-1921. 1

cu. ft. Arrangement: Alphabetical by subject.

These 5" x 7" and 5" x 8" index cards list locations of various Barge Canal construction records, including maps; terminal field books; final estimates for both terminal and Barge Canal contracts; Barge Canal field computation, construction, and cross section books; and unidentified "sheets." The office of State Engineer and Surveyor apparently compiled the index to account for the whereabouts of the working documents relating to construction of the Barge Canal. It is not known exactly which series are being indexed. Most of the field, computation, construction, and cross section books indexed are held by the State Archives. Cards indexing the field, computation, construction, and cross section books provide book number, to whom given, date, purpose, and "where now filed." Cards indexing terminal and Barge Canal contract final estimates provide a brief description of what comprises the estimates, number of pages, total number of "sheets," location, and usually the date when the inventory occurred. Index cards to the maps provide a description of the map and an unidentified set of numbers.

The steam dredge "Marion" was constructed on-site at Mechanicville and used to deepen and widen the channel between Lock 3 and Lock 4 under Contract #72.



Visit Lock 4 Canal Park

Lock 4 Canal Park is open when the State Canal System is operative, usually between May 1 and November 30. Visit the park and hike the 1.5 mile nature trail along the bluff overlooking the junction of the Hoosic and Hudson Rivers. Bring a picnic lunch and watch boats "lock through" from an observation platform. Explore the passages between the mainland and islands by canoe, using the canoe launch at Stillwater just below the dam and hydroelectric plant. The scenery is most impressive in spring when water is running over the Hoosic River rapids, and in the fall when foliage color has arrived. Explore the gorge of Hoosic River when the water level is low in summer, and fish from the tip of the peninsula at the former Vandenburg's Island, at the end of the nature trail.

To visit one of the state's lesser-known but highly scenic state parks, enter from County Route 125, also known as Stillwater Bridge Road. Just east of the canal crossing the entrance road leads south to the lock and park. (NOTE: Do not take the road south of CR 125 immediately east of the Hudson River bridge and west of the canal bridge.) In spite of major changes to the natural landscape resulting from the canal's construction, time has healed the wounds created by the massive excavation shown in the ca. 1910 construction photos, and the area is a scenic and serene place again today.

For further information on the New York State Canal system, contact the New York State Canal Corporation, 200 Southern Boulevard, PO Box 189, Albany, NY 12201-0189 Phone: 1-800-422-6254 or 518-471-5011 (website: <http://www.canals.state.ny.us>) The phone number for Champlain Lock 4 is 518-664-5261.